IMEA
INDIANA MUNICIPAL ELECTRIC ASSOCIATION
SINCE 1941

Safety Message of the Day for IMEA Members



Restoring Power – Verify Before Energizing

Restoring a distribution circuit requires the same attention to detail as establishing a clearance. Before releasing a clearance, verify that all personnel are clear, tools and temporary protective grounds have been removed, and the equipment is ready for energization. Every employee holding a clearance must release it through the established procedure before restoration is authorized. Never rush the restoration process to reduce outage time.

No outage is worth compromising the safety of a lineman.